Statement showing the approximate quantities of work for constructing a Power Sub-Station at the junction of Subedar Chattram and Race Course Road.

No.	Item of work	Rate Unit	Quantities, approximate
1	Earthwork, excavation and filling in basement	C. yd.	831
2	Concrete foundation	C. ft.	6,767
3	Stone in mortar, foundation and basement	"	10,111
4	Stone in mortar, superstructure	"	27,104
5	Stone slabs, 6" thick, exposed parts dressed	S. ft.	1,808
6	Cut-stone arch work	C.ft.	876
7	Quoire stones, 1" draft chiselling	"	708
8	Nicely dressed stone cornice, 6" deep	R. ft.	418
9	Brick cornice, 12" projection	"	385
10	Ornamental parapet wall	"	42
11	Cut-stone pillars with pedestals	No.	10
12	Ornamentation to basement windows	"	4
13	Cement pointing	Sqr.	353·78
14	Mangalore tile flooring on 3" concrete	"	48·55
15	Madras terrace roofing	"	1·69
16	Cement concrete arches on I beams and Mangalore tile flooring	"	42·78
17	Teakwood flooring, 1½" tongued and grooved	"	9·63
18	Mangalore tile roofing on galvanized corrugated iron sheeting	"	77·10
19	Ridge tiles set in mortar	R. ft.	202
20	Zinc sheeting to valleys	"	116
21	Ornamental eave guttering fixed, complete	"	246
22	Cast iron pillars, 11 ft. long	No.	8
23	W. I. trusses, 36 and 31 ft. clear span	"	14
24	Hoisting charges, etc., for the above trusses	"	14
25	W. I. work fixed, complete	Cwt.	262·37
26	Bolts and nuts, etc.	"	·5
27	W. I. pipe railings to galleries	R. ft.	225
28	Teakwood work with wood oiling	C.ft.	822·93
29	Teakwood panelled and glazed doors	S. ft.	479
30	Teakwood glazed windows	"	1,433
31	T. W. circular and semi-circular windows	"	29
32	Painting with 3 coats of silicate paint	Sqr.	150·56
33	Pressed brick in cement	C.ft.	133
34	Cement concrete slabs, 2" thick	"	210
35	Wire gauge shutters	S. ft.	807
36	Fifty lbs. rail to travelling crane	R. ft.	200
37	Galvanized iron rain water down pipes, 4" diameter	"	700

S. G. FORBES,
Chief Electrical Engineer to the Government of Mysore.

BANGALORE DIVISION.

Abstract Notification, dated 4th January 1918.

Attention is invited to the notice calling for tenders for opening out a new road from Kengeri to Tavarekere, published in Part IV of *Mysore Gazette*, dated the 3rd January 1918.

Attention is invited to the notification published in Part IV of the *Mysore Gazette*, dated the 10th January 1918, calling for tenders for gunny bags required for constructing a new Maralvadi Tank at Kankanhalli.

C. VIJAYARANGAM NAIDU,
Executive Engineer.

MYSORE DIVISION.

Notice dated 4th January 1918.

AUCTION SALE OF RATTAN MATS.

1. Notice is hereby given that rattan mats used for the flooring at the Public Offices, Mysore, (approximate quantity 13,000 square feet) will be sold in public auction commencing at 8 A.M., on Sunday the 27th January 1918.

2. The mats will have to be removed from the different office blocks by the approved bidder. The auction will be conducted by the Executive Engineer or by some other officer deputed by him for the purpose.

3. The mats can be inspected during office hours in the several office blocks of the Public office buildings at Mysore.

4. One-fourth of the purchase money should be paid at the time of auction and the remaining before the removal of materials.

N. B.—It may be noted that there is a Government bidding of three pies per square foot already.

Notice dated 17th December 1917.

Attention of the public is invited to the advertisement in detail published in the *Mysore Gazette*, dated 3rd January 1918, calling for tenders for improving the roads at Karapur Camping grounds.

Y. ASWATHANARAYANA RAO,
Executive Engineer.